Certificate No:
TAE000003A
Revision No:
2

This is to certify:

That the Electric Power Cable

with type designation(s)
M2XSH 0,6/1 kV

Issued to
Untel Kablolari San. ve Tic. A.S.
Dilovasi, Turkey

is found to comply with
DNV GL rules for classification – Ships, offshore units, and high speed and light craft

Application :

General power and lighting.

Products approved by this certificate are accepted for installation on all vessels classed by DNV GL.

Rated voltage (kV)	**0,6/1 kV**
Temp. class (°C)	**90**

Issued at **Høvik** on **2019-09-08**

This Certificate is valid until **2024-06-23**.
DNV GL local station: **Istanbul**

Approval Engineer: **Ivar Bull**

for **DNV GL**

Trond Sjåvåg
Head of Section

This Certificate is subject to terms and conditions overleaf. Any significant change in design or construction may render this Certificate invalid.
The validity date relates to the Type Approval Certificate and not to the approval of equipment/systems installed.

Job Id: **262.1-008110-4**
Certificate No: **TAE000003A**
Revision No: **2**

Product description

Type: **M2XSH 0,6/1 kV**
Conductors: Stranded copper class 2 or 5. Tinned on request.
Core insulation: XLPE
Inner covering: Flame retardant halogen free compound
Metal covering: Galvanized steel wire braid
Outer sheath: SHF1

No of cores:	Cross sectional area [mm2]
2	1 – 25
3,4	1 - 120
5	1 - 16
7	1 1,5 2,5
10, 12, 14, 16, 19, 24, 27, 37, 60	1,5

Application/Limitation

The requirements of SOLAS Amendments Chapter II-1, Part D, Reg, 45, 5,2 (provision to be taken to limit Fire Propagation along Bunches of Cables or Wires) are fulfilled without any additional measures,

Type Approval documentation

Data sheets: FR 70-026 Rev. 1 Rev. Tar. 16.12.2010
Test reports: Üntel test reports dated 11/10/2010

Tests carried out

	Release	General description	Limitation
DNVGL-CP-0399	2016-03	Class Programme Electric cables	
IEC 60092-350	2014-08	General construction and test methods of power, control and instrumentation cables for shipboard and offshore applications	
IEC 60092-360	2014-04	Electrical installations in ships - Part 360: Insulating and sheathing materials for shipboard and offshore units, power, control, instrumentation and telecommunication cables.	
IEC 60092-353	2016-09	Electrical installations in ships - Part 353: Power cables for rated voltages 1 kV and 3 kV	
IEC 60332-3-22	2018-07	Tests on electric cables under fire conditions - Part 3-22: Test for vertical flame spread of vertically-mounted bunched wires or cables - Category A	Charred portion of sample does not exceed 2,5m above bottom edge of burner.
IEC 60754-1	2011-11	Test on gases evolved during combustion of materials from cables - Part 1: Determination of the halogen acid gas content	Low Halogen: <0,5% Halogen
IEC 60754-2	2011-11	Test on gases evolved during combustion of materials from cables - Part 2: Determination of acidity (by pH measurement) and conductivity	Halogen free: pH > 4,3 Conductivity < 10µS/mm

	Release	General description	Limitation
IEC 61034-1/2	2013-07 2013-09	Measurement of smoke density of cables burning under defined conditions – Test apparatus, procedure and requirements	Low smoke Light transmittance ≥60%

Marking of product

ÜNTEL – M2XSH – size – IEC 60332 – Cat. A – 0,6/1 kV – Lot nr.

Periodical assessment

The scope of the periodical assessment is to verify that the conditions stipulated for the Type approval are complied with and that no alterations are made to the product design or choice of materials.

The main elements of the assessment are:

- Inspection on factory samples, selected at random from the production line (where practicable)
- Results from Routine tests (RT) and selected type tests (ref. to applicable class programs) checked (if not available these tests shall be carried out)
- Review of type approval documentation
- Review of possible change in design, materials and performance
- Ensuring traceability between manufacturer's product type marking and Type Approval Certificate.

Periodical assessment is to be performed after 2 years and after 3.5 years. A renewal assessment will be performed at renewal of the certificate.

END OF CERTIFICATE